



भाकृअनुप-राष्ट्रीय केला अनुसंधान केंद्र  
(भारतीय कृषि अनुसंधान परिषद)  
थोगमलै रोड, थायनूर पोस्ट,  
तिरुचिरापल्लि - ६२० १०२, तमिलनाडु

ICAR - National Research Centre for Banana  
(Indian Council of Agricultural Research)  
Thogamalai Road, Thayanur P.O.  
Tiruchirapalli - 620 102, Tamil Nadu, India



F.No.9-4(55)/2017-2018-Estt.

/4545,

Date: 01.12.2017

## QUOTATION INVITING NOTICE

Sub : Quotation inviting notice for the work of "Painting of Overhead Water Tank" at the Farm of the ICAR - NRC for Banana, Trichy - Reg

Dear Sirs,

Quotations are invited by the Director, ICAR - NRC for Banana, Trichy, for the "Painting of Overhead Water Tank" at the Farm of the ICAR - NRC for Banana, Trichy, as per details furnished in the tabular column below.

Sl. No.	Name of the work	Qty.
1.	"Painting of Overhead Water Tank" at the Farm of the ICAR - NRC for Banana, Trichy	1 Job.

**NOTE :** RATES FOR MATERIALS AND LABOUR REQUIRED FOR "Painting of Overhead Water Tank" has to be quoted by the contractor.

You are requested to quote your competitive rate (s) for undertaking the above work. Your quotation addressed to the Director, ICAR - National Research Centre for Banana, Thogamalai Road, Thayanur Post, Tiruchirapalli - 620 102 (T.N.), should be uploaded in the e-procurement Central Public Procurement portal on or before **15.12.2017 by 3.00PM.**

The right to accept or to reject all or any of the quotation in part or full is reserved.

Yours faithfully,

  
Asst. Admn. Officer *01/12/2017*

Copy to:

1. The Nodal Officer- CPPP for uploading in CPP Portal
2. The Chairman-PMEC for uploading in NRCB website
3. The Chairman (WLM)
4. The Member Secretary (WLM)

*Mrs CST*  
*M. upload*  
*R. J. huy*



**Name of work : Repair and painting of Over Head Tank at Farm - 35 m  
height- 6 stage bracing- 2 laks litres capacity**

	Description	Qty	Unit	Rate	Amount
	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade , water proof paint APEX ULTIMA				
1	Old work (Two or more coats applied @ 1.43 ltr/ 10 sqm) over existing cement paint surface.	1590.	sqm		
2	Providing and fixing double scaffolding system on the exterior side, upto seven story height made with 40mm dia. M.S. tube 1.5 m centre to centre horizontal & vertical tubes joining using casimo poles scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after .The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge .The elevational area of the scaffolding shall be measured for payment purpose .The payment will be made once irrespective of duration of scaffolding. or providing rope ladder scffolding from top to bottom of water tank.	1 JOB			
	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
3	One or more coats on old work.For hand rails	120	sqm		
	Painting (one or more coats) on CI cast ironpipes, rain water, soil, waste and vent pipes and fittings with black anticorrosive bitumastic paint approved brand and manufacture on old work :				
4	100 mm diameter pipes	20 m	1 job		
5	150 mm diameter pipes	20m	2 job		
6	mason charges for cement repair works if any small damages in the wall, column , floor etc to complete the work including , cement , sand and other materials required for completing the work		1 job		
				<b>Total</b>	